CITY OF STOUGHTON, 381 E. Main Street, Stoughton, WI 53589

ORDINANCE OF THE COMMON COUNCIL			
Amending Section 10-131 of Chapter 10 - Buildings and Building Regulations			
Committee Action:	Public Works recommended approval 3-0 on July 16, 2020		
Fiscal Impact:	N/A		
File Number:	O-16- 2020	**First Reading:**	July 28, 2020
		Second Reading:	

The Common Council of the City of Stoughton do ordain as follows:

Sec. 10-131. - Stormwater management plan requirements.

(b)(4) b. *Runoff rate control—design standards.* Except for redevelopment projects, all stormwater facilities shall be designed, installed and maintained to effectively accomplish the following:

1. Maintain predevelopment peak runoff rates for the one-year, 24-hour storm event (2.~~5~~49 inches over 24-hour duration using the NRCS MSE4 storm distribution)
2. Maintain predevelopment peak runoff rates for the two-year 24-hour storm event (2.~~9~~84 inches over 24-hour duration using the NRCS MSE4 storm distribution).
3. Maintain predevelopment peak runoff rates for the ten-year 24-hour storm event (4.~~2~~09 inches over 24-hour duration using the NRCS MSE4 storm distribution).
4. Safely pass the 100-year 24-hour storm event (6.~~0~~66 inches over 24 hour~~s~~ duration using the NRCS MSE4 storm distribution).

This ordinance shall be in full force and effect from and after its date of publication.

Dates

Council Adopted:_____

Mayor Approved: _____ _____

Tim Swadley, Mayor

Published:_____

Attest:_____ _____

Holly Licht, City Clerk

CITY OF STOUGHTON
DEPARTMENT OF
PLANNING & DEVELOPMENT
207 S. Forrest Street, Stoughton, WI. 53589

(608) 873-6619 www.ci.stoughton.wi.us

RODNEY J. SCHEEL
DIRECTOR

Date: June 23, 2020

To: Public Works Committee

From: Rodney J. Scheel
Director of Planning & Development

Subject: Stormwater Management Ordinance Amendment

We updated Ordinance 10-131 (b)(4)b in 2017. Recently, we discovered a minor change to the numerical standards did not get modified with the adopted version. A draft ordinance amendment has been prepared to correct this issue.

If you have any questions, please contact me.