STRAND ASSOCIATES®
Excellence in Engineering
Since 1946

Strand Associates, Inc.®
910 West Wingra Drive
Madison, WI 53715
(P) 608.251.4843
www.strand.com

May 9, 2023

Mr. Rodney Scheel
Director of Planning and Development
City of Stoughton
207 South Forrest Street
Stoughton, WI 53589

Re: Bickley Court Reconstruction
Contract 4-2023
City of Stoughton, Wisconsin

Dear Rodney,

Bids for the Bickley Court Reconstruction project were opened on May 9, 2023. Five bids were received with the resulting Bid tabulation enclosed.

BKS Excavating, Inc. of Edgerton, Wisconsin, was the apparent low Bidder at $275,840. The Bid included a Bid Bond for 10 percent. The Bid is deemed to be responsive.

The work on Bickley Court was bid earlier this year as part of a larger contract that included work on North Street. The cost of the work on Bickley Court as previously bid was $291,114.06. The previous bids were rejected, and the Bickley Court project was re-bid as Contract 4-2023.

Strand Associates, Inc.® has previously worked with BKS Excavating, Inc. on projects for the City of Stoughton and the City of Lake Mills. For those projects, the owners determined BKS Excavating, Inc. to be responsible.

Please contact me with any questions regarding this project.

Sincerely,

STRAND ASSOCIATES, INC.®

Mark A. Fisher, P.E.

Enclosure

cc: Brett Hebert, Public Works Director, City of Stoughton

Bickley Court Reconstruction														
Contract 4-2023														
City of Stoughton, Wisconsin														
Solicitor: Strand Associates, Inc.														
May 9, 2023 1 PM CDT														
					BKS Excavating, Inc.		Rock Road Companies, Inc.		G-Pro Excavating, LLC		CJP Excavating, LLC		Speedway Sand & Gravel, Inc.	
Section Title	Line Item	Item Description	UofM	Quantity	Unit Price	Extension	Unit Price	Extension	Unit Price	Extension	Unit Price	Extension	Unit Price	Extension
Bickley Court Reconstruction						$275,840.00		$305,604.75		$309,138.00		$333,350.00		$419,342.50
	1	12-IN RCP Storm Sewer	LF	360	$88.00	$31,680.00	$116.75	$42,030.00	$98.00	$35,280.00	$97.40	$35,064.00	$224.00	$80,640.00
	2	7-FT DIA Storm Sewer MH	EA	1	$12,000.00	$12,000.00	$12,282.61	$12,282.61	$14,385.00	$14,385.00	$12,722.50	$12,722.50	$11,545.00	$11,545.00
	3	4-FT DIA Storm Sewer MH	EA	1	$3,450.00	$3,450.00	$4,386.60	$4,386.60	$3,828.00	$3,828.00	$3,900.00	$3,900.00	$6,210.00	$6,210.00
	4	4-IN PVC Sump Pump Pipe	LF	250	$50.00	$12,500.00	$63.30	$15,825.00	$61.00	$15,250.00	$53.00	$13,250.00	$88.70	$22,175.00
	5	Connect Sump Pump Pipe to RCP Storm Sewer Pipe/MH Pipe or MH	EA	5	$850.00	$4,250.00	$813.06	$4,065.30	$500.00	$2,500.00	$430.00	$2,150.00	$995.00	$4,975.00
	6	Granular Backfill for Storm Sewer	T	100	$12.00	$1,200.00	$11.82	$1,182.00	$7.00	$700.00	$13.50	$1,350.00	$16.75	$1,675.00
	7	Common Excavation	LS	1	$55,000.00	$55,000.00	$53,600.00	$53,600.00	$53,400.00	$53,400.00	$74,000.00	$74,000.00	$56,414.00	$56,414.00
	8	Curb and Gutter Removal	LF	950	$6.00	$5,700.00	$6.79	$6,450.50	$6.00	$5,700.00	$6.00	$5,700.00	$6.50	$6,175.00
	9	Concrete Sidewalk and Driveway Apron Removal	SY	190	$10.00	$1,900.00	$11.27	$2,141.30	$45.00	$8,550.00	$34.75	$6,602.50	$62.00	$11,780.00
	10	Crushed Aggregate Base Course	T	1600	$16.00	$25,600.00	$17.48	$27,968.00	$20.00	$32,000.00	$14.25	$22,800.00	$21.90	$35,040.00
	11	Excavation Below Subgrade (EBS)	CY	400	$20.00	$8,000.00	$22.86	$9,144.00	$25.00	$10,000.00	$47.00	$18,800.00	$35.00	$14,000.00
	12	EBS Backfill	T	800	$16.00	$12,800.00	$17.84	$14,272.00	$20.00	$16,000.00	$14.25	$11,400.00	$14.00	$11,200.00
	13	Geotextile for Subgrade Stabilization	SY	1200	$2.00	$2,400.00	$2.18	$2,616.00	$4.00	$4,800.00	$1.94	$2,328.00	$5.55	$6,660.00
	14	30-IN Concrete Curb and Gutter	LF	950	$23.00	$21,850.00	$27.40	$26,030.00	$22.50	$21,375.00	$25.89	$24,595.50	$40.40	$38,380.00
	15	6-IN Concrete Driveway Apron	SF	2400	$8.00	$19,200.00	$9.07	$21,768.00	$7.50	$18,000.00	$8.65	$20,760.00	$15.04	$36,096.00
	16	Asphaltic Concrete Pavement - Lower Course	T	290	$78.00	$22,620.00	$76.00	$22,040.00	$76.00	$22,040.00	$112.75	$32,697.50	$87.55	$25,389.50
	17	Asphaltic Concrete Pavement - Upper Course	T	230	$78.00	$17,940.00	$76.00	$17,480.00	$76.00	$17,480.00	$117.25	$26,967.50	$89.00	$20,470.00
	18	Asphaltic Concrete Pavement Driveway	SF	150	$12.00	$1,800.00	$6.00	$900.00	$6.00	$900.00	$6.75	$1,012.50	$5.80	$870.00
	19	Adjust Water Valve Box to Grade	EA	1	$450.00	$450.00	$169.33	$169.33	$150.00	$150.00	$400.00	$400.00	$444.00	$444.00
	20	Adjust Sanitary Sewer MH Casting INCL New Adjusting Rings	LS	1	$600.00	$600.00	$1,514.17	$1,514.17	$1,500.00	$1,500.00	$600.00	$600.00	$789.00	$789.00
	21	Erosion Control	LS	1	$2,000.00	$2,000.00	$1,450.00	$1,450.00	$2,500.00	$2,500.00	$500.00	$500.00	$10,475.00	$10,475.00
	22	Turf Restoration (Topsoil, Seed, and Mulch)	LS	1	$7,200.00	$7,200.00	$13,603.50	$13,603.50	$18,300.00	$18,300.00	$12,350.00	$12,350.00	$12,840.00	$12,840.00
	23	Traffic Control	LS	1	$4,500.00	$4,500.00	$3,486.44	$3,486.44	$2,500.00	$2,500.00	$3,000.00	$3,000.00	$2,500.00	$2,500.00
	24	Remove and Reset Mailbox	EA	8	$150.00	$1,200.00	$150.00	$1,200.00	$250.00	$2,000.00	$50.00	$400.00	$325.00	$2,600.00
Base Bid Total:						$275,840.00		$305,604.75		$309,138.00		$333,350.00		$419,342.50