LEMKE FENCE OF JEFFERSON, INC.

N3809 BUSINESS 26 JEFFERSON, WI 53549
(920) 674-6211 (920) 674-3101 FAX
dave@lemkefence.com
www.lemkefence.com
lemkefence@yahoo.com

AFA

Established in 1956

City of Stoughton

October 3, 2019

We are pleased to quote you for the fence work as follows:

City Hall:

19' - #420, 2 x 9 x 9'6" high
Fabric - 2" mesh, 9 gauge, 9'6" high chain link, aluminized.

Line Posts - 2 ½ " O.D., galvanized pipe, .095 wall, set 10' or less apart.

Top Rail - 1 5/8" O.D., galvanized pipe, .085 wall.

Bottom Tension Wire – 7 gauge, steel, galvanized, crimped.

Terminal Posts - 3" O.D., galvanized pipe, .160 wall.

Erection – all posts flanged and anchored to existing wall.

60' - #420, 2 x 9 x 4' high added to existing 8' high.
Fabric - 2" mesh, 9 gauge, 4' high chain link, aluminized.

Stub up existing Line Posts – 2 ½ " O.D., galvanized pipe.

Move to top Top Rail – 1 5/8" O.D., galvanized pipe.

Stub up existing Terminal Posts - 3" O.D., galvanized pipe.

Stub up existing Gate Posts – 3" O.D., galvanized pipe.

Leave Gate – 4' wide, single swing.

Add 1 – 4' wide single gate at new building, 8' high.

The above fence complete and erected for $4,727.00

Terms: **Return signed** acceptance copy, balance due upon completion.

* Owner responsible for Permit & Fees where applicable.
* Owner responsible for locating private utility lines.
* Fence lines may have to be adjusted due to buried utility lines.
* Owner to provide survey stakes or fence location.
* Existing fence removed by Lemke

Very truly yours,
LEMKE FENCE OF JEFFERSON, INC.

David Schmitz, President

Accepted by:

Signature Date

David Schmitz 10/3/19
Signature Date

QUOTE GOOD FOR 30 DAYS


30'
Add 4' to existing fence
30'
wall
19'
9'6" high
2439 Cty Rd A


add Gate
existing fence
4th Panel

Outside View

Fence View

Fence View

Inside Stalls